

Generally:

- 1) All aspects of Health and Safety are to be observed during the works
- to protect the contractors and the public.
- All Arisings to be disposed of off-site. Public access including the footpaths and the carpark to be managed Works are required to:
- to exclude the public from areas of work
- All paths to be protected from damage during works. Note there is no vehicular access to north side of river channels.

Objective of works and areas of note:

Tree works are required to be carried out as part of a program of improvements to the Abbey Green park site.

- Remove and prune trees along the river channels in order to allow
- 2) Remove trees around the bowling green in order to improve beneficial

unimpeded access to plant whilst clearing the channels of reeds and


- views in to the bowling green thereby improving security. Remove large over mature trees to reduce the likely hood of trees
- falling in high winds and to create space for remaining trees and to plant a new generation of trees.
- 4) Bring the parks trees into a good state of management and to provide a base from which future maintenance can take place.





DRAFT FOR DISCUSSION





Abbey Green Park, Polesworth

Tree works plan - Sheet 3 of 3

drawing no:	931-30	revision:	*	scale:	1:250 @ A
drawn by:	MP	checked by:	DP	date:	3/12/201
NOTE: Respons	sibility is not accepted	for errors made by	others in scaling	from this	drawing. All construc

information should be taken from figured dimensions only.